

Roseville Public Works, Environment and Transportation Commission

Agenda Item

Date: July 23, 2019

Item No: 4

Item Description: Communication Items

Public Works Project updates:

- Water Booster Station Phase 2
 - The contract for this project was awarded on July 23, 2018.
 - Work will continue through August of 2019.
 - Work includes: HVAC upgrades, electrical upgrades including creation of an electrical room, security upgrades, replacement of two pumps and replacement of some underground piping and valves.
 - Work on this phase is approximately 80% completed.
- 2019 Sewer CIPP
 - The 2019 project involved 4.8 miles of sanitary sewer pipe and one small segment of storm sewer. The project is approximately 95% complete. All work is scheduled to be completed by September.
- Fernwood Lift Station
 - The project includes the upgrade of the lift station. The project was awarded to Minger Construction, Inc on July 8. Work on the lift station will likely begin mid to late summer of 2019.
- 2019 Pavement Management Project
 - This year's pavement management project consists of approximately 8.5 miles of mill and overlay. Work has started in neighborhoods off Western Avenue and Dale Street. Work will continue throughout the summer.
 - The project is about 40% completed. See Attachment B for areas completed.
- City Hall Parking Lot
 - The project consists of reconstructing the parking lot between City Hall and the Maintenance Facility. Work involves the realignment of the access to Civic Center Drive, related storm sewer work, achieving ADA compliance, and replacement of water and sewer mains under the parking lot.
 - The project was awarded to Pember Companies and is scheduled to begin July 29. The project should be completed by October 4th. See attachment C for phasing and parking during the construction.
 - At least 20 parking spots, including handicapped parking, will be available to visitors to City Hall.
- Fairview Trunk Underground Reuse
 - Staff opened bids on this storm water reuse project in Evergreen Park. Bids were significantly higher than expected and the Council rejected bids on July 8.

Metropolitan Council Environmental Services updates:

- Avon street
 - This project is essentially complete. All restoration will be finalized by the end of July.

- Upper Villa
 - This project is essentially complete. All restoration will be finalized by the end of July.

Ramsey County:

- County Road C Reconstruction: Hwy 88 to Long Lake Road
 - The County will be reconstructing County Road C between Highway 88 in St. Anthony and Long Lake Road in Roseville in 2019.
 - Work is underway with traffic down to one lane in each direction.
 - Traffic is anticipated to shift to the west bound lanes in late August.
- County Road C Concrete Rehabilitation: Cleveland Ave to Snelling Ave
 - Work includes concrete maintenance on County C between Cleveland Avenue and Snelling Avenue. Work includes ADA upgrades and concrete joint repairs.
 - Work is currently ongoing with traffic down to one lane in each direction. Work is scheduled to go through mid- August.
- Lexington Avenue Resurfacing, County Road C2 to County Road E
 - The mill and overlay portion of the project will take place in August or September.

Minnesota Department of Transportation updates:

- I-35W MnPASS project - <http://www.dot.state.mn.us/metro/projects/i35wroseville/>
 - Construct MnPASS Express Lanes (one lane in each direction) in the middle of existing I-35W between County Road C in Roseville and Lexington Avenue (County Rd 17) in Blaine.
 - Repave I-35W and ramps between County Road C in Roseville to just north of Sunset Ave (County Road 53) in Lino Lakes.
 - Replace and repair bridges along the project area.
 - Install noise walls on the east side of I-35W just north of the County Road C ramps to County Road D.
 - Contract was awarded in October to Ames Construction which had the winning Design/Build Proposal. Total cost is \$208 million.
 - Major road work is underway.
 - The southbound TH 51 (Snelling Avenue) turn lane to southbound Hamline will be closed for the remainder of the project.
 - All traffic is shifted to the northbound lanes with two through lanes in each direction.
 - The Southbound I-35 ramps to County road C will be closed through November.
 - Rosegate Avenue will be closed through November.

Miscellaneous Updates:

- Campus Solar
 - The Maintenance Building Solar PV System has been installed and is operational. This system is estimated to produce approximately 56% of the energy needed by the Maintenance Building.
- Organics Drop off Site
 - Work has begun on construction of the Organic Drop Off Site at the Leaf Recycling Center off of Dale Street.

City Council Update:

- July
 - Received the 2020-2039 Capital Improvement Plan.
 - Approved the vacation of Albemarle Street right-of-way between Elmer Street and Skillman Avenue.

- Approved resolution prohibiting parking on Larpenteur Avenue between Dale Street and Rice Street

Major Maintenance Activities:

- Street and Storm
 - Assisted Ramsey County in patching their roads prior to Rosefest events.
 - Pre and post sweep of parking lots and streets (both County and City) for Rosefest events.
 - Provided equipment and staff for perimeter security for Rosefest parade.
 - Provided staff and equipment for Rosefest touch a truck event.
 - Completed second sweep
 - Ongoing Streetscape maintenance. Weeding, pruning.
 - Started 4th mow.
 - Re-painting of message pavement markings completed.
 - Ongoing repair of failed catch basins.
 - Ongoing mill and patching of delamination streets.
 - Ongoing spray injection patching of delamination streets.
 - Ongoing compost turning continuing Friday. Deliveries of compost.
 - Ongoing sign repair and installs.
 - Some tree trimming. Minor wind related limbs down.
 - Ongoing debris clearing of pond inlets and outlets related to continual rainfall.
- Water and Sanitary Sewer
 - Continued collecting sanitary sewer flow data every other Friday
 - Completed flushing and inspecting private hydrants
 - Began the 2019 public hydrant painting program
 - Continued the 2019 Sanitary Sewer Cleaning program
 - Completed and distributed the 2018 Consumer Confidence Report
 - Collected water samples for bacteriological and disinfectant by-product testing
 - Continued replacing meter heads and radios
 - Continued working with engineers and contractors on the Booster Station Phase 2 project
 - Continued working with city engineers and consulting engineers on the Fernwood lift station project
 - Continued working with engineers and contractor on County Road C project
 - Started the 2019 valve exercising program
 - Began the 2019 Lead / Copper sampling program
 - Staff participated in OSHA Confined Space Training
 - Completed the painting project inside City Hall

Attachments:

- A: 2019 Project Map
- B: 2019 PMP Status Map
- C: City Hall Parking Lot Phase 1 Plan
- D: July Development Activity Report